



PRODUCT SPECIFICATIONS

Wet Step

CONSTRUCTION

Material: High-density, closed-cell nitrile rubber foam

Thickness: 1/4 inch (0.25")

STANDARDS & TESTING

- Certified high-traction by the National Floor Safety Institute (NFSI)
- Passes flammability standard DOC-FF-1-70
- ASTM C1028-96 Static Coefficient of Friction:
Dry 1.00
Wet 0.98